

To:
Wendt India Ltd
 #69/70, SIPCOT, Industrial Complex
 HOSUR – 635126, Tamilnadu, INDIA

OFFER NO.: **VESP/484 R1/ 24 – 25**

DATE: **20.03.2025**

Kind Attn. : Mr. Ramesh N / 9994525841 / dhanushraj@wendtindia.com

Dear Sir,

We refer your e-mail dated 22nd February 2025 and the various discussion we had regarding your requirement of ed Paint booth and Baking oven. As per the discussion we are submitting herewith our Techno-commercial offer for your review and acceptance.

OFFER FOR PAINT SHOP PLANT EQUIPMENTS

1.0.0 GIVEN DATA:

Maximum Size of component : 3500 mm W X2500 mm H X 3500 mm D
 Maximum weight of the Job : 6000 Kg.

2.0.0 ESSENTIAL EQUIPMENTS FOR THE PROPOSED PAINT SHOP:

SL. No	NAME OF EQUIPMENT	QTY	SCOPE
1	Wet Type Painting Booth + Blower + Exhaust Duct + Electrical control panel	One set	M/s. VITECH
2	Hot Air Oven+ Electrical Heater + Blower + Control Panel	One set	M/s. VITECH
3	Plenum Box with Stand	One set	M/s. VITECH
4	Trolley		Customer Scope
5	EOT		Customer Scope

2.2.0 TECHNICAL DETAILS OF PAINT BOOTH:

S.No	DESCRIPTION	TECHNICAL SPECIFICATIONS
1	Type	Wet Type
2	Air Flow Pattern	Side Down Draft Type
3	Inside working dimension	6.1m (L) x 5.5m (D) x 3.85 m (H)
4	MS – Grating	5.5m x 0.8 m on Both Sides
5	View Glass-5mm with Aluminium Frame	Size 910 x 1200 mm – 2 no's (In the Door)
6	Doors	Hinged Door – one side
8	Top Door	Pneumatic Sliding Door
9	Illumination – LED Flood Light	- 90watts - 6 Nos – Top mounting – Weatherproof – flood light / NFLP
10	Water circulation – Mono block pump.	3 HP – 2 no's Make : Kirloskar / MOC -CI
11	All Pipes and Fittings	2 sets – MS with Butterfly Valve
12	Air Inlet Filter-Mat Type – 10 µ washable	8 Sq.m
	Material of Construction:	
	Tank	Civil -Customer
	Base Frame	MS - ISMC -75 x 40
	Panels Non Wet Area	GI - 18 swg
	Panel Wet Area	SS 304 – 18 swg
	Venturi Plate	SS 304 – 2mm (Dull Finish)

Office: AP-123 AF Block, 6th Street, 11th Main Road, Anna Nagar, Chennai - 600 040, TN, India.

Factory: Survey No 28/3 29/1, Pudukoyal-Arani Road, Vadakanallur Village, Ponneri Taluk, Thiruvallur District – 601 206, TN, India.

Tel: +91-44-2628 0288, 4217 0487, **Mobile:** +91-9444057133 / 30

	Gratings	MS.
	Top Frame	MS SHS 40 x 2mm
15	Finish:	
	Tank	Civil - Customer scope
	Base Frame & Structure	Primer + Final Enamel
	Panels	Primer + Final Enamel
16	Quantity	1 No

2.2.1 TECHNICAL DETAILS OF EXHAUST BLOWER :

Make	Continental / Suitable
Motor HP (NFLP)	15.0 HP/ each
Material of Construction	MS
Drive	Direct drive (self-mounted)
Finish	Casing - Powder Coated / Impeller – Enamel Painted
Quantity	4 Nos. (2 no's on each side of Booth)

2.2.2 TECHNICAL DETAILS OF EXHAUST DUCT:

MOC	GI 22g
Size	700 x 700 mm
Length	40 meters (10 meters x 4 no's for each Blower)
Finish	No Painting

2.2.3. TECHNICAL DETAILS OF PLENUM BOX :

Plenum Box Size	2.5 m (L) X 2.0 m (W) X 1.2 m (H)
Material of Construction	MS – 1.6 mm thick with Flange
Stand	2.5 m Height
Stand MOC	MS Channel – 75 x 40
Quantity	1 No.
Exhaust Duct Size	1.5 L X 1.0 W
MOC of Duct	GI – 0.8 MM thick

3.0.0 HOT AIR OVEN:

S No	DESCRIPTION	TECHNICAL SPECIFICATION
1	Type of the Oven	Batch Type
2	Size of the Oven	5.2 (L) x 4.7 (W) x 4.0 meters (H)
3	No of zone	Single
4	Door Opening	4.0 m (w) x 3.5m (h)
5	Type of Door	Entry & Exit – Single Leaf Hinged Door on one side
5	Material of construction	Main Skeleton – MS 2.5 mm
6		Inner & Outer : GI 18 swg
7	Insulation	100 mm thick – 64 kg/m3
8	Operating temperature	60 ° C - 80 * C (5-6 Hours to reach 80 Deg.C)
9	Heating Media	Electrical Heating System
10	Material Handling	Customer Scope
11	Temperature control	By DTC & Fe – C thermocouple
12	Provisions	1) Hot air suction point
		2) Hot air delivery point

Office: AP 123 AF Block, 6th Street, 11th Main Road, Anna Nagar, Chennai - 600 040, TN, India.

Factory: Survey No 28/3 29/1, Pudukoyal-Arani Road, Vadakanallur Village, Ponneri Taluk, Thiruvallur District – 601 206, TN, India.

Tel: +91-44-2628 0288, 4217 0487, **Mobile:** +91-9444057133 / 30

		3) Air Distribution Openings & Thermo Couple Inserting point
--	--	--

3.1.0 HOT AIR GENERATOR:

SL. No	DESCRIPTION	Quantity
1	Heater Capacity – 42 KW	1 No
2	Main Circulating Blower – 15 HP	1 No
3	Control Panel with 10 meters cable (will be placed near the oven)	1 No
4	Heater Box	1 No

3.2.0 CONTROL PANEL:

LOGIC:

- Electrical heater starts only when Blower is “ON”
- Thermocouple senses the oven temperature
- Digital temperature Controller - Controls the Heaters “ON / OFF”
- Digital temperature Controller - Controls the Conveyor “ON / OFF”

4.0.0 CUSTOMER SCOPE / OFFER EXCLUSION

- All civil work like plat form, foundation, foundation bolts, digging and grouting to install our equipment’s
- All incoming electrical cabling with double earthing to our electrical Panels.
- Crane, Forklift to lift and assemble heavy items during site assembly
- Unloading of material at your site and keeping safely under covered shed
- Jig, Fixture, Flight bar and ‘S’ hook to hold/ hook the component in the Overhead Conveyor
- Scaffolding to assembly the ducts if required to be done by us.
- Free power supply for site fabrication and assembly till the end of Project at 1.0-meter distance near proposed location
- Operator platform/ maintenance platform (if any) – unless otherwise mentioned above
- Any other items not specifically mentioned in our offer

5.0.0 PRICE SCHEDULE – Ex works.

S No	Item Description	Qty	Total Price (in INR)
1	Design, Manufacture and Supply of WET Type Spray Paint Booth	1 Set	Rs. 28,51,800 + GST
2	Design, Manufacture and Supply of Exhaust Duct upto Plenum	40 Meters	Rs. 3,52,000 + GST
3	Plenum Box with Stand as per above mentioned Specification	1 Set	Rs. 97,500 + GST
4	Exhaust Duct per Meter from the Plenum Box	Per Meter	Rs. 15,750 + GST
5	Design, manufacture and Supply of Hot Air oven- Electrical heaters As per the specifications	1 Set	Rs.19,13,500 + GST
6	Erection & commissioning charges for only Paint Booth	LS	Rs.1,95,000 + GST
7	Erection & commissioning charges for only Oven		Rs.1,20,000 + GST
8	Transportation		Client Scope
9	Unloading at Site		Client Scope

Please Note : Any Additional Length of Duct required till Plenum shall be extra @ 8,800 Rupees / meter

Office: AP 123 AF Block, 6th Street, 11th Main Road, Anna Nagar, Chennai - 600 040, TN, India.

Factory: Survey No 28/3 29/1, Pudukkottai-Arani Road, Vadakanallur Village, Ponneri Taluk, Thiruvallur District – 601 206, TN, India.

Tel: +91-44-2628 0288, 4217 0487, **Mobile:** +91-9444057133 / 30

6.0.0 COMMERCIAL TERMS AND CONDITIONS

PRICE BASIS	The price will be ex – works in Chennai
EXCISE DUTY	GST – 18.0% Extra (Or) As applicable at the time of dispatch
FREIGHT CHARGES	Customer scope
UNLOADING AT SITE	Customer Scope
DELIVERY PERIOD	10-12-weeks from the date of receipt of advance with PO or Design Approval Date which ever Later.
PAYMENT TERMS	➤ 50% advance along with Purchase Order ➤ 40% + 100% GST_against pro forma invoice before dispatch ➤ 10% Against Completion of installation.
ERECTION	3-4 Weeks from the date of site clearance or Proforma Payment which ever later
INSPECTION & TESTING	The equipment will be offered for inspection at our works prior to dispatch. The final inspection can be carried out at consignee's site after final erection and commissioning
TECHNICAL DEVIATION	We will supply all the materials as per our offer and decided order only. However, if there are any technical deviations or changes the same should be informed to us and it can be incorporated at extra cost which can be mutually decided upon after discussion and valid order amendment
SUB-CONTRACTING	We reserve the right to buy parts, semi-finished parts from sub-contractors and also to sub-contract any portion of the work as may be found necessary for betterment of the equipment. However, we will be responsible for the complete supply of the equipment.
GUARANTEE	We stand guarantee for the equipment against defective design / faulty workmanship for a period of 12 months from the date of commissioning, whichever is earlier. However, this guarantee does not apply to parts which are subject to normal wear and tear and require periodical replacement such as rubber parts, refractory items, electrical /electronic items, silicon carbide heating element and other perishable items and if the component is found damaged during transit to bad storage, misuse or mishandling of the equipment by you
ESCALATION CLAUSE	The above costing is worked out at present market prices of SS and MS materials and bought out items. Any major price increases shall be decided on mutual understanding.
DEMURRAGE CLAUSE	In case your site is not ready as per the agreed schedule or commissioning is delayed for want of other materials at site a suitable compensation to be paid to us depending on the disturbance cost incurred by VITECH.
FORCE MAJEURE	Our offer is subject to the force majeure clause and as such we will not be responsible for delay in the delivery of equipment due to war, emergency, revolution accidental fire, floods or any such natural calamities which are beyond our control.
VALIDITY	15 days from the date of its submission.
CANCELLATION	Order once placed on us cannot be cancelled without prior concurrence in writing.
JURISDICTION	CHENNAI.

In case of any clarifications feel free to contact us

Thanking you and assuring you of our best services at all times,

With Regards

Mageswaran B

Head - Sales & Marketing

+91 9444057133



Vitech Enviro Systems Pvt Ltd

AP 123, 11th Main Road, Anna nagar, Chennai – 600040

Landline: +91-44-26280288/+91-44-42170847

Email: sales@vitechindia.com / mktg@vitechindia.com

Website: www.vitechindia.in

Office: AP 123 AF Block, 6th Street, 11th Main Road, Anna Nagar, Chennai - 600 040, TN, India.

Factory: Survey No 28/3 29/1, Pudukkottai-Arani Road, Vadakanallur Village, Ponneri Taluk, Thiruvallur District – 601 206, TN, India.

Tel: +91-44-2628 0288, 4217 0487, **Mobile:** +91-9444057133 / 30